

Attachment #3
Asphalt Sealing and Overlay RFP 2022
#2022-01-045

AREA 3

Hippo Area

* Coverage: approximately 222 square yards.

1. Grade/shape the existing rock area along the building as needed to get the area ready for 2" of BP-1 Mix asphalt. Rock to be compacted.
2. Rota-mill butt joints at concrete sidewalk approaches, to approximate depth of 2", to create a smooth transition as possible.
3. Clean loose material and vegetation from area to be paved and prime with SS-1 primer.
4. Overlay area with approximately 2 inches of hot surface mix asphalt, blending and tapering where necessary. Roll asphalt to proper compaction with steel drum vibratory roller.
5. All areas will be barricaded before, during and after this project.

AERIAL MAP



CURRENT CONDITION



Distribution Area

* Coverage: approximately 40 square yards.

1. Roto-mill high spots to an approximate 2" depth to reach uniformity in this area.
2. Clean loose material and vegetation from area to be paved and prime with SS-1 primer. Use BP-1 Mix asphalt.
3. Overlay area with approximately 2 "of hot surface mix asphalt, blending and tapering where necessary. Roll asphalt to proper compaction with steel drum vibratory roller.
4. All areas to be barricaded before, during and after this project.

CURRENT CONDITION



NOTES

The Hippo and Distribution areas have more flexibility in scheduling. We can work closely with the contractor to make accommodations to their schedule.